



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-137-20044-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Tilco, et al.

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Quenzer Well No. 1

Location: CSE-NW Sec. 27 Twp. 1 Rge. (E)(W) 24

County: Norton Total Depth 3664' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

277'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1140' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION very truly yours,

FEB 6 1970

CONSERVATION DIVISION
Wichita, Kansas

M. S. F. Fehle
Conservation Division Agent