

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-137-20027-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Norman D. Fitzgerald,

Complete Address: P. O. Box #5046, Abilene, Texas.

Lease Name: Sumner Well No. 1

Location: CNW-NW Sec. 20 Twp. 1 Rge. (E)(W) 25

County: Norton Total Depth 3647' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

282'--8 5/8" Surface pipe, cement circulated with 225 Sx.
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1240' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1968 Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

A. L. Nichols
Conservation Division Agent