



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-039-20173-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1970
CONSERVATION DIVISION
Wichita, Kansas
8-20-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. W. W. Sauvage of Same has this date requested permission to plug the following described well:

Mr. Sauvage guarantees payment of the plugging fee.

Operator's full Name: W. W. Sauvage

Complete Address: 404 North Penn, Oberlin, Kansas.

Lease Name: Kilzer Well No. 3

Location: SE-SE Sec. 3 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3659' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sauvage was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 875'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent