



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

15-039-20093-06-01

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
AUG 5 1974
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
8-5-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Abererombie Drlg. has this

date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: W.W. Saucage, Inc.

Complete Address: Box 132, Oberlin, Kansas

Lease Name: Kilzer Well No. 1

Location: W/2 SW SE Sec. 3 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3610' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weber was instructed to plug the well as follows:

Gun pits, circulate heavy mud, displace 70 sk cmt at 1545' thru drill
pipe. Heavy mud to 185' displace 20 sk cmt thru drill pipe. Heavy mud to
40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Boo Z. Messing
Conservation Division Agent