

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-039-20093-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. W. W. Sauvage of Sauvage Oil Company, has this date requested permission to plug the following described well:

Mr. Sauvage guarantees payment of the plugging fee.

Operator's full Name: Sauvage Oil Company,

Complete Address: Oberlin, Kansas.

Lease Name: Kilzer Well No. 1

Location: 330' W. of GSW-SE Sec. 3 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3617' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sauvage was instructed to plug the well as follows:

188'--8 5/8" Surface casing, cement circulated with 100 Sx.
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

M. R. Nichols
Conservation Division Agent