



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-039-20182-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent) RECEIVED  
STATE CORPORATION COMMISSION

SEP 24 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
9-24-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Company,

Complete Address: 909 First National Bank Building, Wichita, Kansas.

Lease Name: Fossler Well No. 1

Location: SW-NE Sec. 3 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3620 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

249'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent