



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039-20207-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1971
CONSERVATION DIVISION
Wichita, Kansas
4-19-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. William Kentopp of Platte Valley Oil Co., Inc., has this date requested permission to plug the following described well:

Mr. Kentopp guarantees payment of the plugging fee.

Operator's full Name: Platte Valley Oil Company, Incorporated,

Complete Address: 214 Hillcrest, Ralston, Nebraska.

Lease Name: Daffer Well No. 3

Location: SW-NE Sec. 5 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3610' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kentopp was instructed to plug the well as follows:

22 1/2" -- 8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent