

6 031186

11-18 15-039-20191-00 00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1970
NE NE, SEC. 5, T 15 01 S, R 26 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7267

Operator: Platte Valley OVI Co. Inc.
Name & Address: 253 Hillcrest Center Bldg.
Ralston, Ne. 68127

Lease Name Daffer Well # 2
County Decatur 118.27
Well Total Depth 3639 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 18 Month: Nov Year: 19 88

Plugging proposal received from Jay Buckley

(company name) Platte Valley (phone)

were: 8 5/8" set at 226' w/200 sks. 5 1/2" set at 3555' w/150 sks. PBSD 3555'

D.V. 1661' w/175 sks. Perfs 3328' - 3508'. Order sand and Common Cement
pipe

RECEIVED
STATE CORPORATION COMMISSION
12-20-88
DEC 20 1988

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30PM Day: 18 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3280' w/4 sks Common Cement on sand
w/bailer. Recovered 615' of 4 1/2" w/shots at 810', 1320', and 2010'. Ran tubing to metal
bridge at 750'. Set packer and squeeze below packer through tubing w/30 bbl slurry. Hole
started to circulate through lower shot holes. Released packer circulated cement to surface.
Laid down tubing. Squeeze 8 5/8" w/total of 200 sks cement w/500# Hulls mixed in to max
psi 200#. Close in psi 200#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED / Please preserve this plugging.

DATE 1-6-89
INV. NO. 23516
11-18

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow