

11-10 15-039-20161-00-00

6 031189

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1970.

SE NE, SEC. 5, T. 1 S, R. 26 W/E  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7267

Lease Name Daffer Well # 1

Operator: Platte Valley Oil Co. Inc.  
Name & Address: 253 Hillcrest Center Bldg.  
Ralston Nebraska 68127

County Decatur 117.88  
Well Total Depth 3627 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 10 Month: Nov Year: 19 88

Plugging proposal received from Jay Buckley

(company name) Platte Valley (phone)

were: 8 5/8" set at 288' w/200 sks. 4 1/2" set at 3550' w/100 sks. PBTB 3550'.

Perf 3356' - 3495'. Order sand and Common Cement. Pull pipe. Order 200 sks 65/35 Poz 10%. Gel 2% Dicol 500# Hulls. Halliburton Cement Co. Webbs Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:20PM Day: 10 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3300' w/4 sks Common Cement on sand w/bailer.

Recovered 805' of 4 1/2" casing w/shots at 1300' and 2000'. Ran tubing to 2000'. Circulated cement and Hulls to surface. Laid down tubing. Squeezed 8 5/8" to 500# Max psi. Closed in at 500# psi. w/total of 200 sks cement and 500# Hulls. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If applicable) observe this plugging.

DATE 1-6-89  
INV. NO. 23515  
11-10

Signed Carl Goodrow (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 12-29-88 DEC 29 1988

CONSERVATION DIVISION WICHITA, KANSAS