

11-4 15-039-20178-00-00  
1970

6 031188

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
NE SE, SEC. 5, T. 1501 S, R. 26 W/EX  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7267  
Operator: Platte Valley Oil Co. Inc.  
Name & Address: 253 Hillcrest Center Bldg  
Ralston, Ne 68127

Lease Name Brees Well # 1  
County Dedatur 116.84  
Well Total Depth 3595 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number  
Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 4 Month: Nov Year: 19 88

Plugging proposal received from Jay Buckley

(company name) Platte Valley (phone)  
were: 8 5/8" set at 215' w/190 sks. 4 1/2" set at 3480' w/100 sks. Perf 3291' - 3410'.

Order sand and Common cement. Pnll pipe. Order 200 sks 65/35 10% Dical  
500# Hulls. Halliburton Cement Co. Webb Water Truck.

RECEIVED  
STATE CORPORATION COMMISSION  
12-29-88  
DEC 30 1988

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)  
Conservation Division  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 9:00 PM Day: 4 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3240' w/4 sks Common Cement on

sand w/bailer. Shots at 2015' - 1308'. 825'. Recovered 825' of 4 1/2" casing.  
Ran tubing to 2000'. Circulated cement to surface with 500# Hulls mixed in.  
Laid down tubing. Squeezed 8 5/8" to 300# psi. Close in psi 150#. Plug complete.  
Total 200 sks cement 500# Hulls.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 1-6-89  
INV. NO. 23514  
11-4

Signed Carl Goodrow  
(TECHNICIAN)