

To: 6 031282  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

*8-30*  
API NUMBER 15- 039-20,850-00-00 *274 R*

C NW SW, SEC. 4, T 1 S, R 26 W  
1980 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4964

Lease Name Summer Well # A #1

Operator: DCF Exploration Inc.

County Decatur *117.00*

Name & Address 940 Wadsworth Blvd, Suite 100  
Lakewood, Colorado 80215

Well Total Depth 3600 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 30 Month: August Year: 19 89

Plugging proposal received from Bill

(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8" set at 253' w/170 sks. 4 1/2" set at 3553' w/90 ssk. PBTD 3505'

Perf 3292' - 3302'. Order sand and common cement. Pull pipe. Order

225 sks 65/35 poz 6% gel 500# hulls. Allied Cement Co. LaRue Water

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30AM Day: 30 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 3240' w/4 sks common cement

on sand w/bailer. Shots at 3000' and 2000'. Recovered 4 1/2" casing. Squeezed

8 5/8" w/225 sks cement blend w/500# hulls mixed in to max psi 700.

Close in psi 200#.

RECEIVED  
STATE CORPORATION COMMISSION

SEP - 6 1989

Remarks: (If additional description is necessary, use BACK of this form.)

(I do not intend to conserve this plugging.)

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

INVOICED  
DATE 9-8-89  
INV. NO. 25858

FORM CP-2/3  
Rev. 01-84

*8-30*