

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6 010683

10-20

API NUMBER 15- 147-20,429-00-00

70' S C SE, SEC. 36, T 1 S, R 19 W/E
NE NE
4220 feet from S section line
350 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9597

Operator: One Way Inc.
Name & Address: Box 336
Wray, Colorado 80758

Lease Name Brockett Well # 2
County Phillips 119.44
Well Total Depth 3675 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor One Way Inc. License Number 9597

Address Same

Company to plug at: Hour: _____ Day: 20 Month: Oct Year: 19 89

Plugging proposal received from Howard Peeker

(company name) One Way Inc. (phone) _____

were: Perf casing at 1810' and 1275'. Order 300 sks 65/35 poz

8% gel 500# hulls.

4 1/2" casing at 3673'. Perf at 3465' - 3586'. Elev. 2230' Top pf Dakota at 975.' Anhydrite top 1804'. Ran wireline to T.D. 3646'. Top of fluid at 2000'.

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: _____ Day: 20 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing 25 sks cement then 175 sks cement

w/300# hulls max pres. 700# Holding 600#. Pumped down 8 5/8" 100 sks cement w/200# hulls. Max pres. 600#. Closed w/300#.

Checked casing cement was down 180'. 8 5/8" s.p. down 30'. On November 3, 1989 filled pipe to base of cellar with Redi-mix.

Remarks: Allied Cement Co. (If additional description is necessary, use BACK of this Form)

RECEIVED STATE CORPORATION COMMISSION NOV 14 1989

(If you did not observe this plugging.)

INVOICED

DATE NOV 16 1989
INV. NO. 26485
10-20

Jeb S.

JAN 19 1990

Signed Dale F. Balthazor (TECHNICIAN)