

6 010596

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 147-20,447-00-00

SW NW, SEC. 36, T 1 S, R 19 W/E  
1650 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9500

Lease Name Jackson Well # 1

Operator: Nova Pet. Corp.  
Name & Address: Box 11630  
Salt Lake City, Utah  
84147

County Phillips 119.34  
Well Total Depth 3672 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor \_\_\_\_\_ Company \_\_\_\_\_ License Number 9500

Address \_\_\_\_\_ Same

Company to plug at: Hour: 11:00 AM Day: 4 Month: Mar Year: 19 88

Plugging proposal received from Eldon Miller

(company name) Nova Pet Corp (phone) \_\_\_\_\_

were: Order 150 sks cement 65/35 Poz 10% Ge1 2% Lite.  
4 1/2" at 3671'. Perf 3465' - 3630'. Sanded to 3400' and 4 sks cement.  
Shot pipe at 1500' - and 200'. No recovery - Top cement in 8 5/8" at 60'.  
Elev. 2243' Dakota 1250' = 993'.

Plugging Proposal Received by Dale F. Balthazor  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 AM Day: 4 Month: Mar Year: 19 88

ACTUAL PLUGGING REPORT Pumped down 4 1/2" csg. 140 sks cement.

Pumped down 8 5/8" 10 sks cement. Working Pressure on csg 600#. Closed w/300#.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 9 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: B. J. Titan Cement Co.  
(If additional description is necessary, use BACK of this form.)

(did / observe this plugging.

INVOICED

Signed Dale F. Balthazor  
(TECHNICIAN)  
Dale F. Balthazor

DATE 3-10-88

INV. NO. 20071