

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20027-00-00

Operator's Full Name Norman D. Fitzgerald,

Complete Address P. O. Box #5046, Abilene, Texas.

Lease Name Summer Well No. 1

Location CNW-NW Sec. 20 Twp. 1 Rge. (E) (W) 25

County Norton Total Depth 3617'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kans. License No.

Operation Completed: Hour 12:30 PM Day 18 Month 6 Year 1969

The above well was plugged as follows:

282'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 100 Sx. cement
thru DP from 1240' to 915'. Pulled DP to 310' and displaced 20 Sx. cement thru DP
from 310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack bulls and 10 Sx. cement
to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 6/24/69

INV. NO. 9986-W