

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1969
CONSERVATION DIVISION
Wichita, Kansas

15-137-20025-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Helberg Oil Company,

Complete Address Box #32, Morland, Kansas.

Lease Name Van Cozad Well No. 1

Location CNE-SE Sec. 7 Twp. 1 Rge. (E) (W) 25

County Norton Total Depth 3618'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:30 AM Day 3 Month 6 Year 1969

The above well was plugged as follows:

117'--8 5/8" Surface casing, cement circulated with 100 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 725'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from
180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/5/69
INV. NO. 9886-W

Signed: *H. S. Jichile*
Well Plugging Supervisor