

KANSAS

STATE CORPORATION COMMISSION
RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1970
CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20060-00-00
~~15-20060-00-00~~

Operator's Full Name Will P. Ash,

Complete Address 360 Sutton Place, Wichita, Kansas.

Lease Name Wyatt Well No. 1

Location SW-SW-SE Sec. 21 Twp. 1 Rge. (E) (W) 23

County Norton Total Depth 3644'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #211, Great Bend, Kansas. License No. 637

Operation Completed: Hour 3:00 PM Day 23 Month 11 Year 1970

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated.
3617'--4 1/2" Production casing cemented on bottom with 125 Sx.

Pushed plug to 3400', sanded back to 3375' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (900') and squeezed hole initially with 3 sacks hulls and 12 sacks gel then 100 Sx. cement from 1150' to 825' then 15 sacks gel from 825' to 225' and followed with 25 Sx. cement from 225' to 150' then 3 sacks gel from 150 to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--200#.

Final shut-in pressure-50#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 12/1/70
INV. NO. 2947-W