

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
15-137-00273-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pentagon Corporation,

Complete Address: 533 Petroleum Building, Wichita, Kansas.

Lease Name Applegate Well No. 1

Location CSE-SE Sec. 29 Twp. 1 Rge. (E) (W)24

County Norton Total Depth 3670

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: National Drilling Co.,

Address: 533 Petroleum Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:30p Day 27 Month 3 Year 1963

The Above well was plugged as follows:

287' 8 5/8" surface pipe, cement circulated.
Circulated hole with heavy mdd, set plug @ 540' and displaced 20 Sx
cement thru DP. Heavy mud to 270', set plug with 1/2 sack hulls and
displaced 20 Sx cement thru DP. Heavy mud to 40', set plug with 1/2
sack hulls and 10 sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 4/2/63

INV. NO. 6814-W