

*JF*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Tilco, et al, 15-137-20044-00-00  
Complete Address 200 Sutton Place, Wichita, Kansas.  
Lease Name Quenzer Well No. 1  
Location CSE-NW Sec. 27 Twp. 1 Rge. (E) (W) 24  
County Norton Total Depth 3664'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Leben Drilling, Incorporated,  
Address Box #186, Great Bend, Kansas. License No.         
Operation Completed: Hour 12:30 AM Day 2 Month 2 Year 1970

The above well was plugged as follows:

277'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 900'.  
        
Circulated hole with heavy mud. Pulled DP to 1140' and displaced 100 Sx. cement thru  
DP from 1140' to 815'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from  
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.  
        
      

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
Signed: W. L. Dehler  
Well Plugging Supervisor  
INVOICED  
DATE 2/6/70  
INV. NO. 1382-W