

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20028-00-00

Operator's Full Name Dreiling and Hiko Bell Mining and Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Courtain Well No. 1

Location NE-NE Sec. 12 Twp. 1 Rge. (E) (W) 22

County Norton Total Depth 3833'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 1:30 PM Day 1 Month 7 Year 1969

The above well was plugged as follows:

2 1/2" - 8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1090'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru
DP from 1325' to 1000'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED CONSERVATION DIVISION
Wichita, Kansas

Signed: W. B. Nichols
Well Plugging Supervisor

DATE 7/3/69
INV. NO. 48-W