

KANSAS

R
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

SEP 17 1970 9-17-1970

CONSERVATION DIVISION
Wichita, Kansas

15-039-20179-00-00

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Huff Well No. B-5

Location CSW-SE Sec. 8 Twp. 1 Rge. (E) (W)26

County Decatur Total Depth 3492'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 12:00 PM Day 12 Month 9 Year 1970

The above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 200 Sx. (6 3/4" Hole).
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 70 Sx. cement thru
DP from 1000' to 675'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 9-19-70

INV. NO. 2552-W