

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Wichita, KS 67202

WELL-PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-20,155-00-00

LEASE NAME Ralstin "C"

WELL NUMBER 1

1980 Ft. from S Section Line

810 Ft. from <sup>W</sup>E Section Line

SEC. 12 TWP. 28 RGE. 20W (E) or (W)

COUNTY Kiowa

Date Well Completed 6-20-1973

Plugging Commenced 3-2-04

Plugging Completed 3-12-04

**RECEIVED**  
**MAR 24 2004**  
**KCC WICHITA**

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR LOTUS OPERATING CO., LLC.

ADDRESS 914 E. Douglas Wichita, Kansas 67202

PHONE# (316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-3-04 (date)

Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached?                     

Producing Formation                      Depth to Top                      Bottom                      T.D. 4892'

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf Prod</u>				<u>8-5/8"</u>	<u>614'</u>	<u>None</u>
				<u>5-1/2"</u>	<u>4892'</u>	<u>2224'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from        feet to        feet each set. Plugged off bottom with sand to 4800' and 5 sacks cement, pipe loose @2224'. Tied onto 5-1/2" casing, pumped 300# hulls & 10 sacks gel, fluid came up 8-5/8". Ran 2" tubing to 1250', pumped 15 sacks gel, 40 sacks cement, pulled tubing to 630', pumped 50 sacks cement, pulled to 300', pumped 30 sacks cement, pulled to 40' and circulated 10 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lotus Operating Co., LLC.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of March, 20 04

My Commission Expires:

NOTARY PUBLIC - State of Kansas  
**IRENE HERZBERG**  
My Appt. Exp. 8-24-05

Notary Public