

RECEIVED

MAR 23 2004

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 December 2003 See or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Roberts and Murphy, Inc.

Address: P.O. Box 7125 Shreveport, LA 71101

Phone: (318) 221-8601 Operator License #: 4145

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 6-27-03 (Date)

by: Scott Alberg (KCC District Agent's Name)

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No

Producing Formation(s): List All (If needed attach another sheet) 5393'-5397' Depth to Top: Bottom: T.D. 5403'-5418' Depth to Top: Bottom: T.D. 5640

API Number: 15 - 033-20719 - 00 - 01

Lease Name: Box Ranch

Well Number: B-2

Spot Location (QQQQ): E/2 - SE - SE/4 - 1270' Feet from [] North / [X] South Section Line

510' Feet from [X] East / [] West Section Line

Sec. 10 Twp. 35S S. R. 20 [] East [X] West

County: Comanche

Date Well Completed: 02/17/88

Plugging Commenced: 03/12/04

Plugging Completed: 03/17/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Prod Surf and CIBP.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log-Tech set CIBP @ 5316' & dump bailed 2 sxs cmt on plug. Shot csg @ 2712' & csg was free. Pulled/LD 6 jts. Pulled remainder of the 65 Jts (2695.2') of 4 1/2" casing. Ran tbg to 1000', pumped 15 sxs get & 50 sxs 60/40 Pozmix cmt. Pulled tbg to 656' & pumped 50 sxs 60/40 Pozmix cmt. PULLED tub to 314' & pumped 80 sxs 60/40 Pozmix cmt & circulated to surface. Plugging witness & approved by Steve Middleton.

Name of Plugging Contractor: Pratt Well Service, Inc. License #: 5893

Address: P.O. Box 847, Pratt, KS 67124

Name of Party Responsible for Plugging Fees: Roberts & Murphy, Inc.

State of Kansas County, Pratt, ss.

Kenneth C. Gates, President (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kenneth C Gates, President

(Address) P.O. Box 847, Pratt, KS 67124

SUBSCRIBED and SWORN TO before me this 22 day of March, 20 04

Amy Robertson Notary Public My Commission Expires: 3/13/08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

AMY S. ROBERTSON Notary Public - State of Kansas My Appt. Expires 3/13/08