

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-097-10186-00-00

API NUMBER Comp. 10-16-62

LEASE NAME Zimmerman "D"

WELL NUMBER 1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 35 TWP. 27S RGE. 20W (E) or (W)

COUNTY Kiowa

Date Well Completed 10-16-1962

Plugging Commenced 2-25-04 3-12-04

Plugging Completed 3-12-04

RECEIVED  
MAR 24 2004  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR LOTUS OPERATING CO., LLC

ADDRESS 914 East Douglas Wichita, Kansas 67202

PHONE# (316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-3-04 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached?                     

Producing Formation                      Depth to Top                      Bottom                      T.D. 4977'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>				<u>8-5/8"</u>	<u>350'</u>	<u>None</u>
<u>Prod</u>				<u>4-1/2"</u>	<u>4968'</u>	<u>700'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from        feet to        feet each set.  
Ran 2" tubing to 4000', loaded the hole with 13 bbls. of water 1-3/4 BPM @2500#. Pumped 25 sacks 60/40 pos. Pulled tubing up to 2500'. couldn't circulate hole. Pulled 2" tubing out. Pumped 26 bbls. water to 500# down 4-1/2" casing, shut in. Cut pipe loose @700', ran 2" tubing to 714' and pumped 25 sacks cement, pulled tubing up to 350' and circulated 100 sacks cement to surface. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Lotus Operating Co., LLC.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of March, 2004

[Signature]  
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas  
IRENE HERZBERG  
My Appt. Exp. 8-24-05

Form CP  
Revised 05-