

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

MAR 19 2004

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior, Inc.

Address: P.O. Box 399

Phone: (620) 275-2963g Operator License #: 4058

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: March 17, 2004 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [X] No

Producing Formation(s): List All (If needed attach another sheet)

Cherokee Depth to Top: 4192 Bottom: 4288 T.D. 4300

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-145-00745-00-00

Lease Name: Holman

Well Number: 2

Spot Location (QQQQ): SE - NE -

1980 Feet from [X] North / [ ] South Section Line

660 Feet from [X] East / [ ] West Section Line

Sec. 22 Twp. 20 S. R. 19 [ ] East [X] West

County: Pawnee

Date Well Completed: 9/22/61

Plugging Commenced: 3/17/04

Plugging Completed: 3/18/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Cherokee, oil/water, 4251', 4262', 8 5/8", 342', None. Row 2: 4 1/2", 4299', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded off bottom from 4180' to 4263 PBDT, Put 4 sacks of cement on top of sand. Mix and pump 100 sacks of 60/40 poz, 6% gel with 500 pounds of hulls to 1200', cement placed 1200' to 3200', let sit overnight, Perforate casing @ 500', Mix 150 sacks of 60/40 poz, 6% gel, pump 75 sacks down 4 1/2" casing until pressure built to 1100 psi, shut in with 950 psi on casing, Pump 75 sacks down 8 5/8" annulus until pressure reached 500 psi, shut in with 450 psi. Well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: N. Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Corsair

(Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 18th day of March 20 04

Bernice Moore My Commission Expires: 2/1/06 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

