

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

MAR 17 2004

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

RJM Company

Lease Operator: R.J.M. Oil Company

Address: P.O. Box 265, Claflin, Kansas 67525

Phone: (620) 587-3910 Operator License #: 30458

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: February 22nd, 2004 (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 2910' Bottom: 3399' T.D. 3400'

API Number: 15-053-20785-00-00

Lease Name: Kozisek Twin

Well Number: #2-NW NE NE NW

Spot Location (QQQQ): 50'WC - N/2 - NE - SW 330' Feet from North / South Section Line

1930' Feet from East / West Section Line

Sec. 21 Twp. 16 S. R. 10 East West

County: Ellsworth

Date Well Completed: October 2nd, 1982

Plugging Commenced: March 11th, 2004

Plugging Completed: March 12th, 2004

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

M.I.R.U. Run in hole with bailer to bottom - OK. Spot sand and got in 55 bbls. total fluid. Waited for sand to fall. Spot 5 sxs cement. Rigged up jacks-removed slips and broke out head. Work casing 6" total stretch. Went in hole with knife and tried to cut @ 1800'-had some trouble with knife. Finally cut and pulled casing to 1375'. Pump 150# hulls and 35 sxs. Pull casing to 1050'-pump 35 sxs-150# hulls; 640'-100# hulls and 35 sxs; 300'-pump 100# hulls-35 sxs. Pull rest of pipe. Hole stayed full. Tore down - tallied pipe and moved off.

Name of Plugging Contractor: D.S.&W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: R.J.M. Oil Company RJM Company

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Notary Public stamp for Karen J. Mitchell, State of Kansas, My Appt. Expires 4/13/06

SUBSCRIBED and SWORN TO before me this 16th day of March, 2004. My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202