

API NUMBER Spud 10/7751 15-147-0074706-01

LEASE NAME Center Hufstutter Unit

Dixon #1

WELL NUMBER \_\_\_\_\_

2970 Ft. from (S)N Line of Section (circle one)

3630 Ft. from (E)W Line of Section (circle one)

SPOT LOCATION SW - SE - NW - \_\_\_\_\_

SEC. 32 TWP. 01 S. RGE 18 (E) or (W)

COUNTY Phillips

Date Well Completed 10/51

Date Plugging Commenced 12/15/98

Date Plugging Completed 12/16/98

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 14200 E. Central

CITY, STATE, ZIP Wichita, KS 67230

PHONE# (316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well Input  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/15/98 (date)

by Dennis Hamel, District #4 (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Filed with plugging application

Producing Formation(s) Lansing Kansas City Depth to Top 3407 Bottom 3522 T.D. 3522

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
				8-5/8	189	0
				5-1/2	3250	0

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Ran tubing to 1700'. Mixed 4 sx hulls in first part of 150 sx cement. Pulled tubing to 800'

Mixed 1 sx hulls in first part of 105 sx cement. Pulled tubing. Wait overnight. Ran tubing to top

of cement @ 1100'. Mixed 3 sx hulls in first part of 80 sx cement and circulated to surface.

Pulled tubing and topped off. Pumped 25 sx between 8-5/8 & 5-1/2. Shut in w/ 100 PSIG.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Fischer Pipe Testing, Inc.

License No. 32332

Address P.O. Box 273 Ellis, KS 67637-0273

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary L. Reed Agent  
(Signature) of Operator or (Operator) of above-described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Gary Reed

(Address) 14200 Brookline Ct. Wichita, KS 67230

SUBSCRIBED AND SWORN TO before me this 7th day of January, 19 99

Dana R. Clothier  
Notary Public

My Commission Expires: 11/13/2000



RECEIVED  
STATE CORPORATION COMMISSION  
1-11-1998  
JAN 11 1999  
CONSERVATION DIVISION  
Wichita, Kansas