

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00#2-00-00
API NUMBER N/A
LEASE NAME Center Huffstutter Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER Bennett #1
2970 Ft. from S Section Line
2310 Ft. from E Section Line
SEC. 32 TWP. 1 RGE. 18 (EXX(W))
COUNTY Phillips
Date Well Completed 10/18/51
Plugging Commenced 7/30/86
Plugging Completed 7/30/86

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A If not, is well log attached? Submitted with plugging application

Producing Formation Lansing/K.C. Depth to Top 3433' Bottom 3533' T.D. 3548'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/K.C.	Oil & water	3433'	3533'	5 1/2"	3547'	-0-
				8 5/8"	192'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 150 sx cement, 5 sx hulls down 5 1/2" casing @ 200 psi max. pres. S.I.P. 50 psi.
Pumped 75 sx cement, 3 sx hulls down 8 5/8" @ 50 psi max. pres. S.I.P. 25 psi

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address P. O. Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.


R. D. Reber, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Reber, Jr.

(Address) 400 N. Woodlawn, Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 86

My Commission Expires: _____



AUG 8 1986

B & R Drilling, Inc.
Bennett No. 1

SW SW NE - Section 32-1-18W
Phillips County, Kansas

15-147-00742-00-00

Total Depth: 3547'

Comm: 9-14-51

Comp: 9-23-51

Well Log

Casing

8 5/8" Set @ 192'
5 1/2" Set @ 3547'

Cement

125 sacks of Ideal
250 Sacks of Bulk

Formation

Depths

Shale-Shells-Sand	192
Shale-Shells	600
Sand-Shale	940
Shale-Shells	1050
Sand-Shale	1535
Shale-Shells	1570
Redbed-Shale-Shells	1780
Anhydrite	1860
Shells-Shale	1950
Lime-Shale	2745
Lime	2810
Lime-Shale	3480
Lime	3515
Lime-Shale	3547'

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

I hereby certify that the above information is

true and correct to the best of my knowledge.

Violet Keller

Notary Public

Subscribed and sworn to before me this 28th day of September, 1951.

COPY

Clara Lummel

Notary Public

My commission expires: 6-17-54

THANK YOU.

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

JUL 24 1986