

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00755-00-00
API NUMBER Spud 6/18/50

LEASE NAME Center Huffstutter Unit
Hufstutter E #3

WELL NUMBER
330 Ft. from (S)N Line of Section (circle one)
4950 Ft. from (E)W Line of Section (circle one)

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.
ADDRESS 14200 E. Central
CITY, STATE, ZIP Wichita, KS 67230
PHONE#(316) 733-5600 OPERATORS LICENSE NO. 5242
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION SW - SW - SW
SEC. 32 TWP. 01 S. RGE 18 W or (W)
COUNTY Phillips
Date Well Completed 6/50
Date Plugging Commenced 12/16/98
Date Plugging Completed 12/16/98

The plugging proposal was approved on 12/15/98 (date)
by Dennis Hamel, District #4 (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Filed with plugging application

Producing Formation(s) Lansing Kansas City Depth to Top 3356 Bottom 3442 T.D. 3442

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
				8-5/8	176	0
				5-1/2	3429	0

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Ran tubing to 1700'. Mixed 4 sx hulls in first part of 130 sx cement. Pulled tubing to 850'. Mixed 3 sx hulls in first part of 50 sx cement and circulated to surface. Pulled tubing and pumped 25 sx cement down casing. Pumped 25 sx cement down 8-5/8 - 5-1/2 annulus and pressured to 100 PSIG.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Fischer Pipe Testing, Inc.
License No. 32332
Address P.O. Box 273 Ellis, KS 67637-0273

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1999

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

CONSERVATION DIVISION

Gary L. Reed Agent
(Knows) of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary L. Reed

(Address) 14200 Brookline Ct. Wichita, KS 67230

SUBSCRIBED AND SWORN TO before me this 7th day of January, 19 99

Dana R. Clothier
Notary Public

My Commission Expires: 11/13/2000

