

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

15-147-00750-00-00

LEASE NAME Davis

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 4

2310 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Petroleum Management, Inc.

SEC. 32 TWP. 1 RGE. 18 ~~XXXXX~~ W)

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

COUNTY Phillips

PHONE# (316) 686-7287 OPERATORS LICENSE NO. 5242

Date Well Completed 9/29/50
~~Aug. 1950~~

Character of Well Oil

Plugging Commenced 8/8/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/8/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Lansing-K.C. Depth to Top 3423' Bottom 3548' T.D. 3548'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing-K.C.</u>	<u>Oil</u>	<u>3445</u>	<u>49</u>	<u>8 5/8</u>	<u>250</u>	<u>None</u>
		<u>3497</u>	<u>3501</u>			
		<u>3531</u>	<u>35</u>	<u>5 1/2</u>	<u>3545</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped down 5 1/2" w/50 sx. cement w/3 sx hulls (18 Bbl) - 14 sx. gel (28 Bbl) - wiper plug - 150 sx cement (53 Bbl). Hook to 8 5/8". Pump 50 sx cement w/4 sx hulls (18 Bbl) - 10 sx gel (20 Bbl) - 50 sx cement (18 Bbl). Cement 60-40 Pozmix, 10% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. D. Reber, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Reber, Jr.

(Address) 400 N. Woodlawn, Wichita, KS 67208

RECEIVED
SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 85
STATE CORPORATION COMMISSION

SEP 6 1985
My Commission Expires:
CONSERVATION DIVISION
Wichita, Kansas


BONNIE BROWN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Mar. 1, 1989

Bonnie Brown
Notary Public