

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

15-147-00745-00-00

Phillips County, Sec. 32 Twp. 1S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SW SE SE

Lease Owner Lawrence Supply Company

Lease Name Davis Well No. 7

Office Address Box 448 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed September 24, 1951 19

Application for plugging filed December 7, 1953 19

Application for plugging approved December 9, 1953 19

Plugging commenced December 9 19 53

Plugging completed December 11 19 53

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3560 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226'	None
				5-1/2"	3555'	1175'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3510' to 3470' and ran 4 sacks of cement. Mudded hole to 230', set a 10' rock bridge and ran 15 sacks of cement. Mudded hole to 40', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. B. Lawrence (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Lawrence Supply Co.

(Signature) Lawrence
Box 448, Great Bend, Kans.

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1954

My commission expires Sept. 15, 1956
Notary Public.

PLUGGING
FILE REC 32 T. 1 S. 18 W
BOOK PAGE 142 LINE 41

1-30-54
CON DIVISION
Kansas

Copy

15-147-00745-00-00

WELL LOG DAVIS NO. 7

A. R. Peters, Lease Owner

Section 32, Twp. 1S, Rge. 18W

Garvey Oil, Contractor

Location: SW SE SE

Commenced: September 15, 1951

Phillips County, Kansas

Completed: September 24, 1951

Rotary Total Depth: 3560'

Casing: 226' of 8 5/8" w/150 sax
3559' of 5 1/2" w/150 sax

All figures below indicate bottom of formation:

226 Surface Sand & Shells
1100 Shale
1325 Sand
1370 Shale
1500 Shale & Sand Streaks
1835 Shale & Red Bed
1844 Anhydrite
1985 Shale
2130 Shale & Lime
2300 Shale & Shells
2395 Shale
2510 Shale & Broken Lime
2640 Shale, Lime & Shells
2800 Shale & Lime
2910 Shale & Shells
3125 Lime & Shells
3210 Lime
3345 Lime & Shale
3560 Lime

Anhydrite: 1835

3560' R.T.D.

I hereby certify that the above is a true and correct log of the abovementioned well.

GARVEY OIL

By _____
Eric H. Jager

STATE OF KANSAS)
) SS.
COUNTY, SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 29th day of September, 1951.

(Charlotte Weidman)
Notary Public

My commission expires: October 13, 1954

PLUGGING
TWP. 32 1 18W
PAGE 142 LINE 41