

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-00746-00-01

API NUMBER N/A

LEASE NAME Davis

WELL NUMBER 8

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 32 TWP. 1 RGE. 18 (E) (W)

COUNTY Phillips

Date Well Completed Jan. 1952

Plugging Commenced 8/8/85

Plugging Completed 8/8/85

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE# (316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Lansing-K.C. Depth to Top 3399' Bottom 3520' T.D. 3520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	Oil	3413	17	8 5/8	240	None
		3448	52			
		3465	69	5 1/2	3519	None
		3492	96			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped down 5 1/2" w/50 sx cement, 3 sx hulls (18 Bbl), followed by 14 sx gel (28 Bbl) - wiper plug - 150 sx cement (53 Bbl). Hook to 8 5/8". Pumped 50 sx cement w/4 sx hulls (18 Bbl) - 10 sx gel (20 Bbl) - 50 sx cement (18 Bbl). Cement 60-40 Pozmix, 10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. D. Reber, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Reber, Jr.

(Address) 400 N. Woodlawn, Wichita, KS 67208

Subscribed and sworn to before me this 30th day of August, 19 85

Bonnie Brown
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 SUBSCRIBED AND SWORN TO
 SEP 6 1985
 9-6-85
 CONSERVATION DIVISION
 Kansas
 Wichita, Kansas
 On Exp

BONNIE BROWN
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. Mar. 1, 1989