

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-00749-00-0001

API NUMBER N/A

LEASE NAME Davis

WELL NUMBER 3

1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 32 TWP. 1S RGE. 18 (XXX) (W)

COUNTY Phillips

Date Well Completed March 1950

Plugging Commenced 8/8/85

Plugging Completed 8/8/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A if not, is well log attached? N/A

Producing Formation Lansing-K.C. Depth to Top 3430' Bottom 3552' T.D. 3552'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	Oil	3529	31	8 5/8	210	None
		3542	46	5 1/2	3548	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump down 5 1/2" w/50 sx cement w/3 sx hulls (18 Bbl) - 14 sx gel (28 Bbl) - wiper plug - 150 sx cement (53 Bbl). Hook to 8 5/8". Pump 50 sx cement w/4 sx hulls (18 Bbl) - 10 sx gel (20 Bbl) - 50 sx cement (18 Bbl). Cement 60-40 Pozmix, 10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. D. Reber, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Reber, Jr.

(Address) 400 N. Woodlawn, Wichita, KS 67208

RECEIVED
 STATE CORPORATION COMMISSION
 SUBSCRIBED AND SWORN TO before me this

SEP 6 1985

Commission Expires: _____
 Wichita, Kansas

BONNIE BROWN
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. Mar. 1, 1989

Bonnie Brown
 Notary Public