

15-137-20265-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-137-20,265 -
00-00

LEASE NAME Hadley "A" #1

WELL NUMBER _____

SPOT LOCATION C SE NE

SEC. 30 TWP. 1s RGE. 24w or (

COUNTY Norton

Date Well Completed _____

Plugging Commenced 4/9/84

Plugging Completed 4/16/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F & M Oil Company, Inc.

ADDRESS 422 Union Center, Wichita, Ks. 67202

PHONE # 316 262-2636 OPERATORS LICENSE NO. #5313

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 327' | none |
| | | | | 4 1/2" | 3680' | 1129' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with 4 sacks cement, sand & 4 sacks cement to 3400'. Shot pipe at 2010', 1450', & 1129'. Pulled 28 joints of pipe. Plugged well with 3 hulls, 26 gel, 100 cement, 14 gel, 8 5/8 plug, & 70 sacks 50/50 poz 6% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.


MAY 16 1984

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1984



Irene Hoover
Notary Public

My Commission expires:

Form CP-4
Revised 06-