

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

RECEIVED  
STATE CORPORATION COMMISSION  
9-15-89  
SEP 15 1989

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-039-20,478-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Management, Inc. OPERATORS LICENSE NO. 5242

ADDRESS 400 N. Woodlawn, Suite 201 PHONE # (316) 686-7287

LEASE (FARM) Powell WELL NO. 1 WELL LOCATION NE NE SE COUNTY Decatur

SEC. 7 TWP. 1S RGE. 26 (E) or (W) TOTAL DEPTH 3590' PLUG BACK TD 3587'

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 206' CEMENTED WITH 145 SACKS

CASING SIZE 4 1/2" SET AT 3575' CEMENTED WITH 250 SACKS

PERFORATED AT 3575-87' (Open Hole) 3361-65', 3451-53'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Cement over perms, Pull casing @<sup>±</sup>1200',  
Cement 1200', mud to 250', cement 250' to surface

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9:00 a.m. September 25, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don Keener PHONE # (913) 434-2042

ADDRESS Box H Plainville, KS 67663

PLUGGING CONTRACTOR Petroleum Management, Inc. LICENSE NO. 5242

ADDRESS Box H Plainville, KS 67663 PHONE # (913) 434-2042

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]  
(Operator or Agent)

DATE: 9/13/89

(4)

15-039-20478-00-00

DRILLERS LOG

No. 1 Powell-Martin

CASING RECORD:	COMPANY:	Petroleum Management, Inc.	DESCRIPTION:
8 5/8" @ 206' w/145 sx cement	CONTRACTOR:	Red Tiger Drilling Company	NE/4 NE/4 SE/4 Sec. 7-T1S-R26W Decatur County, Kansas
4 1/2" @ 3,575' w/250 sx cement	COMMENCED:	December 17, 1979	
TOTAL DEPTH: 3,590'	COMPLETED:	December 23, 1979	ELEVATION: 2,503' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	212	
Shale	212	1595	
Shale & Sand	1595	1656	
Sand	1656	1748	
Shale & Sand	1748	1860	
Shale	1860	1969	
Anhydrite	1969	1997	
Shale	1997	2120	
Shale & Red Bed	2120	2690	
Shale & Lime Streaks	2690	2973	
Lime	2973	3100	
Lime & Shale	3100	3258	
Lime	3258	3590	
RTD		3590	


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 14th day of January, 1980.

Joyce A. Hagermann  
Notary Public

 Joyce A. Hagermann  
NOTARY PUBLIC  
Sedgwick County Kansas  
My Appt. Exp. 10-18-80

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1980  
CONSERVATION DIVISION  
Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
 KEITH R. HENLEY CHAIRMAN  
 RICH KOWALEWSKI COMMISSIONER  
 MARGALEE WRIGHT COMMISSIONER  
 JUDITH McCONNELL EXECUTIVE DIRECTOR  
 FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
 SHARI FEIST ALBRECHT, DIRECTOR  
 200 Colorado Derby Bldg.  
 202 W. 1st Street  
 Wichita, KS 67202-1286  
 (316) 263-3238

15-039-20478-00-00

September 15, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

Petroleum Management, Inc.  
 400 N. Woodlawn, Suite 201  
 Wichita, KS 67208

Powell 1  
 NE NE SE  
 07-01-26W  
 Decatur County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*

Shari Feist Albrecht  
Director

District: #4 2301 E. 13th

Hays, KS 67601

(913) 628-1200