

KANSAS

JL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

SEP 24 1970
CONSERVATION DIVISION
Wichita, Kansas
9-24-1970

15-039-20182-00-00

Operator's Full Name Aylward Drilling Company,

Complete Address 909 First National Bank Building, Wichita, Kansas.

Lease Name Fossler Well No. 1

Location SW-NE Sec. 3 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3620'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.

Operation Completed: Hour 4:30 PM Day 21 Month 9 Year 1970

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru
DP from 1125' to 800'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Dreibel*
Well Plugging Supervisor

DATE 9/25/70
INV. NO. 2582-41