

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sauvage Oil Company, 15-039-20093-00-00

Complete Address: Oberlin, Kansas.

Lease Name Kilzer Well No. 1

Location 330' W. of CSW-SE, Sec. 3 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3617

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:00 PM Day 19 Month 6 Year 1969

The Above well was plugged as follows:

188'--8 5/8" Surface casing, cement circulated with 100 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1969

CONSERVATION DIVISION
Wichita, Kansas

June 23, 1969

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/24/69

INV. NO. 9983-W

Signed: N. S. Nichols
Well Plugging Supervisor