

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1974

CONSERVATION DIVISION
Wichita, Kansas
8-5-1974

15-039-20093-00-01

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name W. W. Sauvage, Inc.

Complete Address Box 132, Oberlin, Kansas 67749

Lease Name Kilzer Well No. 1

Location W/2 SW SE Sec. 3 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3610'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:45 P Day 1 Month 8 Year 1974

The above well was plugged as follows:

RTD 3610' 8 5/8 esg set at 188' ewe. Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, displaced 70 sk cmt at 1545' thru drill pipe.

Heavy mud to 185' displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set

cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/6/74

INV. NO. 9677-a

Signed: Res. J. Massey
Well Plugging Supervisor