

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20230-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 3 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
4-3-1972

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Summer Well No. C-2

Location NW-SE Sec. 4 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3605'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 11:00 AM Day 28 Month 3 Year 1972

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement  
thru DP from 1125' to 800'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru  
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. S. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 4-3-72

INV. NO. 5468-W