

KANSAS

KS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1970
CONSERVATION DIVISION
Wichita, Kansas
8-20-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20173-00-00

Operator's Full Name W. W. Sauvage,

Complete Address 404 North Penn, Oberlin, Kansas.

Lease Name Kilzer Well No. 3

Location SE-SE Sec. 3 Twp. 1 Rge. (E) (W)26

County Decatur Total Depth 3659'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:00 AM Day 17 Month 8 Year 1970

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. ceamt to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dinkel
Well Plugging Supervisor

DATE 8/20/70
INV. NO. 2416-W