

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-147-00819-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SE

SEC. 25 TWP. 1 RGE. 19 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mc Kenzie Box 414

Operator Lawrence & Meltzer Oil Address Great Bend, Kans

Field _____ County Phillips

Total Depth 3545 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 218' circulated with cement - 5 1/2" at 3544' with

170 sax cement behind. Perforated at 3529'.

Filled with chat to 3520', set 4 sax cement, pulled 1700' 5 1/2",

filled hole with mud to 210', set rock and 15 sax cement,

filled with mud to 35', set rock and 10 sax cement to bottom

cellar.

PLUGGING
FILE SEC 25 T 1 R 19 W
BOOK PAGE 117 LINE 14

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1951
CONSERVATION DIVISION
WICHITA, KANSAS

Edna Seely
District Conservation Agent

Date 10-14-51