

KANSAS

Form CP-3
Rev. 6-4-68

AL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1972

CONSERVATION DIVISION
Wichita, Kansas
(585)

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Don H. Peaker 15-147-00433-00-00

Complete Address Box 1595 Pueblo, Colorado 81002

Lease Name Brockett "A" Well No. 1

Location NE SE NE Sec. 36 Twp. 1 Rge. (E) (W) 19

County Phillips Total Depth 3630'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 12:30 P Day 13 Month 10 Year 1972

The above well was plugged as follows:

Total Depth 3630' 8 5/8 csg set at 200' cwc Cmt. Mat. 50-50 poz cmt W/6% gel.

4 1/2 csg set at 3629' cw 150 sk cmt.

4 1/2 csg PBTD 3599' W/top perf. (3439-3443)

Filled 4 1/2 csg W/sd (3400-3599) Dumped 4 sk cmt W/dump bailer. (336503400)

Cutoff and recovered 1505' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls - 70 sk cmt - 10 sk gel & water - released 8 5/8 plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 10/17/72

INV. NO. 6474-W