

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-19052-00-00

FILE NO. 110-4

LOCATION SE SW SE

SEC. 25 TWP. 1 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hammond

Operator D. G. Hansen Address Logan, Kans

Field _____ County Phillips

Total Depth 3666 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 270' circulated with cement - 5 1/2" at 3665'
with 150 sax cement behind, perforations at 3448'
Filled with chat to 3435', set 4 sax cement with dump
bailer, pulled 2262' 5 1/2", filled hole with mud to 250',
set rock and 15 sax cement, filled with mud to 35'
set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 25 T 1 R 19
BOOK PAGE 110 LINE 4

Edon P. Pety
District Conservator, Agent

RECEIVED
Date 9-22-51

SEP 28 1951

CONSERVATION DIVISION
Wichita, Kansas