

DISTRICT CONSERVATION AGENT'S REPORT

*B*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

13-147-19051-00-00

FILE NO. \_\_\_\_\_

LOCATION NE SE SE

SEC. 36 TWP. 1 RGE. 19 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Essert

Operator Petroleum ~~Inc~~ Management, Inc. Address 1019 Cent Bldg Wichita,

Field \_\_\_\_\_ County Phillips

Total Depth 3551 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 192' circulated with cement. 5 1/2" at 3550' with  
150 sax cement behind.

Filled with sand to 3540', set 4 sax cement with dump bailer,  
pulled 1500' 5 1/2" - heavy mud to 190', set rock and 15 sax cement,  
mud to 35', set rock and 10 sax cement to bottom cellar.

*E. Perry*

District Conservation Agent

Date 5-31-56

JUN 1 1956

PLUGGING  
FILE SEC 36 T. 1 R. 19W  
BOOK PAGE 63 LINE 27

GCP