


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-00816-00-00

FILE NO. \_\_\_\_\_

LOCATION NE NW SE

SEC. 36 TWP. 1 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. A-1 Lease Jackson

Operator Co-op Refg Assn Address Great Bend, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3536 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 218' circulated with cement - 5 1/2" at 3534' with  
225 sax cement behind - top perforations at 3409'.

Filled with sand and chat to 3400', set 4 sax cement  
with dump bailer, pulled 1700' 5 1/2", filled hole with mud to  
200', set rock bridge and 15 sax cement, filled with mud  
to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1951

CONSERVATION DIVISION  
Wichita, Kansas

Edwin J. Kelly  
District Conservation Agent

Date 7-7-51

PLUGGING  
FILE SEC 36 TWP. 1 RGE. 19  
BOOK PAGE 90 LINE 44