

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-00986-00-00

FILE NO. 125-3

LOCATION SW SE NE

SEC. 36 TWP. 1 RGE. 19

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Brockett Est

Operator Lawrence & Meltzer Oil Address Great Bend, Kans

Field _____ County Phillips

Total Depth 3570 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 242' circulated with 150 sax cement - 5 1/2" 3569'

with 175 sax cement behind.

Filled with chat and rock to 3500' set 5 sax cement with dump

bailer - pulled 1400' 5 1/2" - filled hole with mud to 240',

set rock and 15 sax cement, mud to 35', set rock and 10 sax

cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1952

CONSERVATION DIVISION
Wichita, Kansas

Edward J. Kelly
District Conservation Agent

Date 5-6-52

PLUGGING

FILE SEC 36 T 1 R 19
BOOK PAGE 125 LINE 3