

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-00817-00-00

FILE NO. _____

LOCATION NE NE NE

SEC. 36 TWP. 1 RGE. 19 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Brook Est BROCKETT Est.

Operator Lawrence & Meltzer Oj Address Great Bend, Kans

Field _____ County Phillips

Total Depth 5528 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 222' circulated with cement - 5 1/2" at 3527' with 200
sax cement behind - Perf at 3497'.

Filled with chat to 3490' set 4 sax cement with dump bailer,
pulled 1400' 5 1/2", filled hole to 220', set rock and 15 sax cement,
filled with mud to 35', set rock and 10 sax cement to bottom
cellar.

PLUGGING
FILE SEC. 36 TWP. 1 RGE. 19 W
BOOK PAGE 118 LINE 22

J. P. [Signature]
District Conservation Agent
STATE CORPORATION COMMISSION
Date 10-19-51
RECEIVED
OCT 22 1951
CONSERVATION DIVISION
Wichita, Kansas