

RECEIVED

MAR 19 2004

KCC WICHITA

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

FORM CP-1  
Rev.03/92

**WELL PLUGGING APPLICATION FORM**

(PLEASE TYPE FORM and File ONE Copy)

15-153-00036-00-01

API # 15- 6/59 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

12/04

WELL OPERATOR Murfin Drilling Co., Inc. KCC LICENSE # 30606  
(owner/company name) (operator's)  
ADDRESS 250 N. Water, Suite 300 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 267-3241  
LEASE Texaco Cahoj WELL# 50 SEC 18 T.1S R. 34W (East/West)

SE SE SE, Rawlins Co. SPOT LOCATION/QQQQ COUNTY  
330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)  
330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# E-16,643

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 446 CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 4761' CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGE PLUGS SET: 4230-38,4268-78,4308-17. CIPB @4320'  
ELEVATION 3184 TD 4778  
(GL or KB)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING In accordance with the rules and regulations of the State of Kansas.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? no

If not explain why? \_\_\_\_\_

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

John Turner Prod Supt. PHONE# (785 ) 462-6781  
ADDRESS PO 661, 1040 Plains Ave. City/State Colby, KS 67701

12/04

PLUGGING CONTRACTOR Murfin Drilling Co., Inc. KCC LICENSE # 30606  
(company name) (contractor's)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS PHONE # (316) 267-3241

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Nov 2003

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

DATE: 3/18/04 AUTHORIZED OPERATOR/AGENT: Tom W. Nichols

WICHITA, KANSAS  
July 2, 1959

RECEIVED

MAR 19 2004

KCC WICHITA

Skelly No. 1 Cahoj "B"  
(Lease No. 66092)  
SE SE SE - 18-18-34W  
Rawlins County, Kansas  
Cahoj Pool

Mr. Howard S. Bryant  
Tulsa, Oklahoma

FIELD NOTES

GENERAL

Contractor Claude Wentworth Drilling Co.  
Rotary Tools  
Drilling Commenced June 12, 1959  
Drilling Completed June 30, 1959

CASING

8-5/8" set @ 446' w/300 sacks.

GEOLOGICAL DATA

Elevation: 3186 D.F., 3184 Gr.  
Samples from 3600' to 4776' R.T.D., and drilling time from  
3600' to 4776' R.T.D.

Formation Tops:

Niobrara	1125	(/2061)	Schlumberger MLL
Ft. Hays	1520	(/1666)	" "
Base Ft. Hays	1574	(/1612)	" "
Carlile	1627	(/1559)	" "
Greenhorn	1797	(/1389)	" "
Dakota	1923	(/1263)	" "
Morrison	2576	(/610)	" "
Permian	2760	(/426)	" "
Base Elaine	2787	(/399)	" "
Top Stone Corral	3017	(/169)	" "
Base Stone Corral	3058	(/128)	" "
Chase	3164	(/22)	" "
Admiral	3700	(-514)	" "
Topeka	3876	(-690)	" "
Heehner	4018	(-832)	" "
Leavenworth	4024	(-838)	" "
Lansing	4075	(-889)	" "
Base Kansas City	4334	(-1148)	" "
Marmaton	4373	(-1187)	" "
Cherokee	4510	(-1324)	" "
Cherokee sand	4586	(-1400)	" "
Mississippi line	4694	(-1508)	" "
Pre-Cambrian Quartzite	4774	(-1588)	Samples
Rotary Total Depth	4778,	4' Pen. Quartzite	

DRILL STEM TESTS

Topeka: 3876 (-690)  
H.D.S.T. #1: 3862-3930 (0-54' Pen.) Open 1 1/2 hours.  
Recovered: 110' Mud. IHHP: 1220/30",  
FP's: 20-50, FHHP: 1040/30".

al

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Murfin Drilling Co., Inc.  
250 N. Water, Ste 300  
Wichita, KS 67202

March 24, 2004

Re: TEXACO CAHOJ #50  
API 15-153-00036-00-01  
SESESE 18-1S-34W, 330 FSL 330 FEL  
RAWLINS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely



David P. Williams  
Production Supervisor