

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

RECEIVED
MAR 25 2004
KCC WICHITA

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-135-²⁴²⁶³~~214263~~-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation KCC LICENSE # 5003
(owner/company name) (operator's)

ADDRESS: 8080 E. Central CITY: Wichita
STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737
LEASE: Pavlu 'A' WELL#: 1-2 Section 2 Township 19s Range 24w
100' SE of C W/2 SW SPOT LOCATION/QQQQ COUNTY: Ness
1249 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)
731 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 212' KB CEMENTED WITH 150 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 2304 G.L. 2313 K.B. T.D. 4352 PBTD _____ Anhydrite Depth 1565-1605
(Stone Corral Formation)
CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders on 03/18/04 at 2:00 pm from Steve Pfeifer. Plugged in following manner beginning
at 11:30 am on 03/19/04: Used 225 sx of 60/40 Poz; 6% Gel; 1/4# Floseal. Heavy mud in hole; bottom plug
at 1605' - 50sx, 2nd plug at 750' - 80sx, 3rd plug at 375' - 30sx, 4th plug at 240'-40sx, top plug at 40'-10 sx, cemented
to surface. Rathole - 15sx, no mousehole. Plug down at 2:00 pm on 03/19/04. Allied Cementing ticket #18256.
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Lanny Saloga/Gary M. Talbott Phone#: (316) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR : Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 9:30 am on March 20, 2004.
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 03/19/04 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

RECEIVED

MAR 25 2004

KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Pavlu 'A' 1-2

LOCATION:	100' SE of C W/2 SW	Section	2	T 19s	R 24w
API:	15-135-214263-0000	Ness County, Kansas			

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 03/10/04
COMPLETED: 03/19/04

TOTAL DEPTH:	DRILLER	4352	FEET
	LOGGER	4358	FEET

Ground Elevation: 2304
KB Elevation: 2313

LOG

0 -	4 FEET	Surface Soils
4 -	180 FEET	Sand and Clay
180 -	1565 FEET	Redbeds
1565 -	1605 FEET	Anhydrite (Driller's)
1605 -	2400 FEET	Shales and Salt
2400 -	4352 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud @ 2:45 am on 03/10/04. Drilled 12-1/4" hole to 215'. Ran 5 joints of new 23# 8-5/8" surface casing tally 200.81' set at 211.81' KB, Cemented with 150 sx Common; 3% CC, 2% Gel. Plug down at 8:00 pm on 03/10/04. Cement did circulate. Swift Cementing ticket #6612. Welded straps on bottom 3 joints & welded collars on remainder.

Plugging Data:

Received plugging orders on 03/18/04 at 2:00 pm from Steve Pfeiffer. Plugged in following manner beginning at 11:30 am on 03/19/04: Used 225 sx of 60/40 Poz; 6% Gel; 1/4# Floseal. Heavy mud in hole; bottom plug at 1605' - 50sx, 2nd plug at 750' - 80sx, 3rd plug at 375' - 30sx, 4th plug at 240'-40sx, top plug at 40'-10 sx, cemented to surface. Rathole - 15sx, no mousehole. Plug down at 2:00 pm on 03/19/04. Allied Cementing ticket #18256.

DEVIATION SURVEYS

3/4 degree(s) at	215	feet
1-1/2 degree(s) at	3865	feet
3/4 degree(s) at	4275	feet