

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-039-20,800-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Brito Oil Company OPERATORS LICENSE NO. 4629

ADDRESS 200 E. First, #413 PHONE # (316) 263-8787

LEASE (FARM) Wiggins WELL NO. 1 WELL LOCATION NW SW SW COUNTY Decatur

SEC. 17 TWP. 1 RGE. 26 ~~(X)~~ or (W) TOTAL DEPTH 3500' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 268' CEMENTED WITH 200 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug at 1880'-20 sacks; 2nd plug at 1235'-100 sacks
+ 1 sack celoflake; 3rd plug at 315'-40 sacks; 4th plug at 40' to solid bridge-10 sacks; rathole-10 sacks; all
cement 60/40 posmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? no
(If not, explain) _____ Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-1-86 5:30 p.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Bill Craig, Sr. PHONE # (913) 674-2876

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton
(Operator or Agent) _____
Jack K. Wharton, Secy/Treas 1-7-1987
DATE: 1-6-87 JAN 7 1987

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Starting Date 11-24-86
month day year

(see rules on reverse side)

API Number 15- 039-20800-00-00

OPERATOR: License # 4629
Name Brito Oil Company, Inc.
Address 200 E. First, Suite 413
City/State/Zip Wichita, KS 67202
Contact Person Raul F. Brito
Phone (316) 263-8787

NW SW SW Sec. 990 Twp. 1 S, Rg. 26
990 Ft. from South Line of Section
4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, Kansas

Nearest lease or unit boundary line 990' feet
County Decatur

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name Wiggins Well # 1
Ground surface elevation 1100 feet MSL

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 60
Depth to bottom of usable water 1100
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 250
Conductor pipe required None
Projected Total Depth 3500 feet
Formation Granite Wash

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 11-12-86 Signature of Operator or Agent Title President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. 1

This Authorization Expires 5-17-87 Approved By 11-19-86

S.P. 268
Bill Craig

11/25/86

W-Well at rig will
be plugged by WW driller.

DH

NW NW SW Sec. 17 Twp. 1 S, Rg. 26 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

not opp.

- 1st plug @ Arbuckle feet depth with 20-25 sxs of 60/40 posmix, 6% gel, 3% ca.c.l.
- 2nd plug @ Middle of Anhydrite feet depth with 25-30 sxs of 60/40 posmix, 6% gel, 3% ca.c.l.
- 3rd plug @ .50' below base Dakota feet depth with 80-100 sxs of 60/40 w/ one bag Floseal If short string
- 4th plug @ .50' below surface casing feet depth with 40-50 sxs of 60/40 posmix, 6% gel, 3% ca.c.l.
- 5th plug @ Top 40' feet depth with 10 sxs of 60/40 posmix, 6% gel, 3% ca.c.l.
- (2) Rathole with 10-15 sxs (b) Mousehole with 10 sxs

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.
In Addition: Call district office after well is either plugged or production casing is cemented in.

(Call 7 a.m. to 5 p.m. workdays)

District office use only:

API #15- 039-20800
Surface casing of feet set with sxs at hours, 19
Alternate 1 or 2 surface pipe was used.
Alternate 2 cementing was completed @ ft. depth with sxs on 19
Hole plugged 19, agent