



15-039-20289-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1974
8-13-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Abercrombie Drlg. has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Leland R. Baird

Complete Address: Logan, Ks.

Lease Name: Anthony Well No. 1

Location: CNE SE Sec. 16 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3524 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weber was instructed to plug the well as follows:

Gun pits, circulate heavy mud, displace 70 sk emt at 1500' thru drill pipe. Heavy mud to 185' displace 20 sk emt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk emt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent